DEPARTMENT OF AGRICULTURE.

OFFICE OF THE AGRICULTURAL ENGINEER, BANGALORE.

Abstract Notification dated 2nd August 1939.

Attention of the public is invited to the notification No. 5 of 1939-40, dated 1st August 1939, calling for tenders for constructing a Cattle Stall for the Cattle Breeding Station at Hunsur, published in the *Mysore Gazette*, Part VI, dated 3rd August 1939 in page 1524.

Notification No. 3 of 1939-40, dated 1st August 1939.

Notice is hereby given that separate sealed tenders will be received at the office of the Agricultural Engineer, up to 2 P.M. on 18th August 1939, for constructing—

(1) Inspector's Quarters for the Agricultural School, Somanahalli.
(2) Combined Cattle Stall, Implement Shed and Watchman's Quarters for the Agricultural School, Somanahalli.
(3) Quarters for the Fieldman and Maistry for the Agricultural School, Somanahalli.
(4) Cooly Lines for the Agricultural School, Somanahalli, near Maddur.

2. An approximate estimate of quantities for each of the above works is given below separately. The quantities are not guaranteed. The works should be completed within one month from the date of acceptance of the tender.

3. Earnest money of Rs. 75 for the Inspector's Quarters and Rs. 40 for each of the other works should be remitted under Revenue Deposits, at the Main Huzur Treasury, Bangalore, or Maddur Taluk Treasury, with a chellan duly filled in by the tenderer. The tender should be superscribed according to the nomenclature given, items 1, 2, 3 and 4, as noted in para 1. The tenders will be opened at 2-30 P.M. on the 18th August 1939.

4. Subject to the formal sanction of the Director of Agriculture, the acceptance of each tender rests with the Agricultural Engineer, who does not bind himself to accept the lowest or any tender, or assign any reason whatsoever for the rejection of any tender.

5. Within a week of the acceptance of the tender, the successful tenderer will be requested to furnish a cash security of 5 per cent of the value of the work and to execute the usual contract bond, in default of which his tender will be considered as cancelled, and the security deposit forfeited.

6. The name of the successful competitors whose tenders have been accepted will be notified in due course.

7. After the acceptance of successful tenders, the earnest money deposited in the refused tenders will be arranged to be returned to the parties.

8. Rates overtendered will on no account be enhanced.

9. Quotations must be written in words as well as in figures.

10. The measurements checked by the Agricultural Engineer will have to be accepted as final.

11. Tenders for one or more of the works indicated in para 1, will be accepted.

12. The successful tenderer will be required to use the Mysore Cement and paint.

Statement showing the approximate quantities of Works.

Constructing Inspectors' Quarters for the Somanahalli Agricultural School.

No.	Items of work	Unit	Quantity
1	Earthwork excavation for foundation	C.yd.	21
2	Lime concrete in mortar	C.ft.	154
3	Size stone in mud	,,	313
4	Cement concrete	,,	154
5	Burnt brick in mud	,,	1,096
6	Burnt brick in mortar	,,	343
7	Teak wood doors with panels, etc., complete	S.ft.	113
8	Teak wood windows with shutters, iron bars, etc., complete	,,	71
9	R. C. ventilators	,,	4
10	Teak wood wrought and put up	C.ft.	50·3
11	Roofing with Mangalore tiles on teak wood reepers	Sqr.	9·7
12	Flooring 4″ cement concrete and cement plastering	,,	4·7

No.	Items of work	Unit	Quantity
13	Plastering with 2 coats of mortar	Sqr.	
14	Whitewashing, 2 coats	,,	
15	Colour wash, 2 coats	,,	
16	Painting wood works, 2 coats	,,	
17	Tarring wood works, 2 coats	Lump sum	
18	Wood oiling, 2 coats	Sqr.	
19	Pointing with cement	,,	
20	Providing sinks with out-lets	Each	
21	Building ovens in kitchen and in bathroom	Lump sum	
22	Mortar band including cornices	R.ft.	68
23	Plastering with cement	Sqr.	

Constructing a Combined Cattle Stall, Implement room and Watchman's Quarters for the Somanahalli Agricultural School.

1	Earthwork excavation for foundation	C.yd.	16
2	Rough stone in mud	C.ft.	528
3	Walls in mud	,,	1,070
4	Plastering	Sqr.	15·4
5	Do with cowdung wash	,,	8·5
6	Whitewashing	,,	22
7	Roofing with Mangalore tiles on areca reepers	,,	14·1
8	Manger earth filled bamboo work	R.ft.	24
9	Jungle wood wrought and put up	,,	925
10	Flooring with gravel on well rammed earth	Sqr.	6 8
11	Teak wood doors with ply wood panels	S.ft.	59
12	Teak wood windows with ply wood shutters, iron bars, etc., complete.	,,	36
13	Painting doors and windows	Sqr.	2·1
14	Tarring wood work	,,	12·1
15	Stone slabs 6" thick	S.ft.	
16	Tilters for the animals	Lump sum	

Constructing a Quarters for the Maistry & Fieldman, Agricultural School, Somanahalli.

1	Earthwork excavation for foundation	C.yd.	
2	Stone in mud	C.ft.	251
3	Mud walls	,,	383
4	Plastering with mud and whitewashing	Sqr.	8·5
5	Plastering with mud, cowdung wash and cement washing	,,	6·5
6	Teak wood doors with ply wood panels, etc., complete	S.ft.	54
7	Teak wood windows with ply wood shutters, iron bars, etc, complete	,,	22·5
8	Jungle wood wrought and put up	,,	241
9	Roofing with mangalore tiles on areca reepers	Sqr.	6·1
10	Flooring with gravel on well rammed earth	,,	
11	Stone slabs 6" thick	S.ft.	79
12	Pointing with cement	Sqr.	0 75
13	Tarring wood work	,,	4
14	Painting wood work	,,	1·6
15	Providing sinks with outlet	Each	

Constructing Cooly Lines for the Agricultural School, Somanahalli.

1	Earthwork excavation for foundation	C.yd.	17
2	Stone in mud	C.ft.	560
3	Mud walls	,,	1,730
4	Stone slabs 6" thick	S.ft.	99
5	Teak wood doors with ply wood panels, etc., complete	,,	72
6	Teak wood windows with ply wood shutters, iron bars, etc., complete	,,	27
7	Jungle wood wrought and put up	R.ft.	578
8	Roofing with mangalore tiles on areca reepers	Sqr.	11 6
9	Flooring with gravel on well rammed earth	,,	5·2
10	Plastering with mud and white washing	,,	

No.	Items of work	Unit	Quantity
11	Plastering with mud, cowdung wash and cement wash	Sqr.	9·6
12	Pointing with cement	,,	1·1
13	Tarring wood work	,,	..
14	Painting wood work	,,	2·1
15	Providing sinks with outlets	Each	4

Notification No. 4 of 1939-40, dated 1st August 1939.

Notice is hereby given that sealed tenders will be received at the office of the Agricultural Engineer, up to 2 P.M. on the 18th August 1939, for constructing a new activated charcoal production house on the Irwin Canal Farm, eight miles from Mandya.

2. An approximate estimate of quantities for the above work is given below. The quantities are not guaranteed. The work should be completed within one month from the date of acceptance of the tender.

3. Earnest money of Rs. 65 in cash should be remitted under Revenue Deposits, at the State Huzur Treasury, Bangalore or Mandya District Treasury, with a chellan duly filled in by the tenderer. The tender should be superscribed "Tender for constructing Activated Charcoal Production House on the Irwin Canal Farm, Mandya." The tenders will be opened at 2-30 P.M. on 18th August 1939.

4. Subject to the formal sanction of the Director of Agriculture, the acceptance of tender rests with the Agricultural Engineer, who does not bind himself to accept the lowest or any tender or assign any reason whatsoever for the rejection of any tender.

5. Within a week of the acceptance of the tender, the successful tenderer will be required to furnish a cash security of 5 per cent of the value of the work and to execute the usual contract bond in default of which his tender will be considered as cancelled and the security deposit forfeited.

6. The name of the successful competitor whose tender has been accepted will be notified in due course.

7. After the acceptance of the successful tender, the earnest money deposited on the refused tenders will be arranged to be returned to the parties.

8. Rates overtendered will on no account be enhanced.

9. Quotations must be written in words as well as in figures.

10. The tender amount checked by the Agricultural Engineer, will have to be accepted as final.

Statement showing the approximate quantity of work.

Constructing an Activated Charcoal Production House at the Irwin Canal Farm, Mandya.

No.	Items of work	Unit	Quantity
1	Earthwork excavation for foundation	C.ft.	27
2	Lime concrete with stone jelly	C.ft.	292
3	Stone in mud	,,	598
4	Burnt brick in mud	,,	1,563
5	Burnt brick in mortar	,,	93
6	Stone slabs 6" thick	S.ft.	135
7	Teak wood doors with panelled shutters, etc., complete ..	,,	69
8	Teak wood windows with panelled shutters, iron bars, etc., complete	,,	80
9	Expanded metal ½" mesh, fixed to teak frame	,,	302
10	Fixing iron trusses of 24' span	Each	4
11	Fixing R. S. joists 5"×6"	,,	6
12	Flooring with lime concrete 4" thick and cement plastered ..	Square	6 6
13	Flooring with gravel on well rammed earth	,,	8·3
14	Plastering with mortar 2 coats	,,	34·5
15	Whitewashing 2 coats	,,	34·5
16	Painting iron and wood work	,,	9

Notification No. 2 of 1939-40, dated 1st August 1939.

Notice is hereby given that sealed tenders will be received at the office of the Agricultural Engineer, up to 2 P.M. on the 18th August 1939, for erecting a colony house for the Somanahalli Agricultural School, near Maddur.

2. An approximate estimate of quantities for the above work is given below. The quantities are not guaranteed. The work should be completed within one month from the date of acceptance of tender.

3. Earnest money of Rs. 25 in cash should be remitted under Revenue Deposits at the State Huzur Treasury, Bangalore, or Maddur Taluk Treasury, with a chellan duly filled in by the tenderer. The tender should be superscribed "Tender for erecting poultry run and a colony house for the Somanahalli Agricultural School, near Maddur." The tenders will be opened at 2-30 P.M. on 18th August 1939.

4. Subject to the formal sanction of the Director of Agriculture, the acceptance of tender rests with the Agricultural Engineer, who does not bind himself to accept the lowest or any tender or assign any reason whatsoever for the rejection of any tender.

5. Within a week of the acceptance of the tender, the successful tenderer will be required to furnish a cash security of ten per cent of the value of the work and to execute the usual contract bond in default of which his tender will be considered as cancelled and the security deposit forfeited.

6. The name of the successful tenderer whose tender has been accepted will be notified in due course.

7. After the acceptance of the successful tender, the earnest money deposited on the refused tenders will be arranged to be returned to the tenderers.

8. Interim payments will on no account be allowed.

9. Quotations must be written in words as well as in figures.

10. The measurements checked by the Agricultural Engineer will have to be accepted as final.

Statement showing the approximate quantities of works.

No.	Description of work	Per	Quantity
	Colony House.		
1	Earthwork excavation for foundation	C.yd.	7
2	Burnt stone pillars 1'×6"	S.ft	148
3	Burnt brick in clay	..	210
4	Casuarina poles for rafter and Bresseumers. 5" diameter ..	R.ft.	342
5	Roofing with thatch on thick bamboos matting and ½" mesh wire-netting, (wire-netting will be supplied departmentally)	S.yr.	..
6	Mud-plastering from top of wall to the roof level (wire-netting will be supplied separately)	S.yr.	800
7	White-washing and whitening	Square	3·5
8	Colour-washing	..	3·5
9	Flooring with gravel and tar emulsion, rolled and smoothed well	..	6·0

M. G. SINGARACHAR,
Agricultural Engineer.

GOVERNMENT HIGH SCHOOL, KOPPA, BANGALORE.

Notification dated 1st August 1939.

The refund of fees of the following students remain undisbursed. They should prefer their claim within 30 days from this date. Otherwise the amount will be remitted to the Treasury and no claim will be considered.

	Rs.	a	p.
(1) B. Mannaji Rao, III year E of 1938-39	2	0	0
(2) C. Chamaiah, III year B of 1938-39 Medical Fee ..	0	8	0

M. A. NARAYANA IYENGAR,
Head Master.